



05/02/2025

Ottawa Lake
ASI # 58-0003CA
7555 Whiteford Rd
Ottawa Lake, MI 49267

All sampling and testing are performed in accordance with ASTM Section 4 Construction Volume 04.02 and MDOT Standard Specification for Construction 2020 Table 902-1 and 902-2 Section 703.

2006-MDOT 6AA Limestone

Procedure	Sieve/Test	Average	Unit	MDOT 6AA
ASTMC136 &117 MTM 109&108	1 1/2" (37.5mm)	100.0	%	100-100
	1" (25mm)	100.0	%	95-100
	3/4" (19mm)	85.0	%	
	1/2" (12.5mm)	43.2	%	30-60
	3/8" (9.5mm)	22.1	%	
	#4 (4.75mm)	3.4	%	0-8
	#8 (2.36mm)	1.6	%	
	#16 (1.18mm)	1.2	%	
	#30 (.6mm)	1.1	%	
	#50 (.3mm)	1.0	%	
	#100 (.15mm)	1.0	%	
	#200 (75µm)	1.0	%	
	Wash Loss (#200/75um)	0.9	%	0.0-2.0

All sampling and testing are performed in accordance with ASTM Section 4 Construction Volume 04.02 and MDOT Standard Specification for Construction 2020 Table 902-1 and 902-2 Section 703.

Name/Title

Scott George / QC Tech